

		<p>9. Air Conditioner (1.5) Ton with 4 KVA Stabilizer (in CSR):</p> <p>Electrical Work</p> <ul style="list-style-type: none"> • An electrical board as defined at "D" (3 in JSR & 5 CSR): 08 Nos. • Mirror Optic twin tube light fitting (2 in JSR & 4 in CSR) • Copper Plate earthing • All the wiring should be 3/20 copper wires for computers and lights etc. and 7/20 for air conditioners, server and UPS. • A 6 WAY MCBDB for UPS boards and two industrial power points for Air Conditioners and one for UPS. • Earthing wire should be 1/18 copper unit at CSR. 04 Nos. • Ceiling fans (2 in JSR & 2 IN CSR) • Provision for installing Air Conditioner unit at CSR: 04 Nos. • Capacity: 1.5 Ton with 4KVA Voltage Stabilizer (For CSR): 	<p>01 No.</p> <p>08 Nos.</p> <p>06 Nos.</p> <p>04 Nos.</p> <p>01 No.</p>
2.	Ghatshila	<p>Civil work</p> <ol style="list-style-type: none"> 1. Counter with Aluminum grill with glass. <ul style="list-style-type: none"> • Aluminum window made out of standard aluminum extruded sections of medium weight, fully fixed as per design complete with 5mm Plain glass foxed with EPDM gaskets over fabrication over aluminum grill of 6 Square bars @ 6" c/c both ways. • P/F 19mm thick white marble top counter with edge molding. • Letters and logo of approved shade and pattern. 2. Aluminum partition with door is to be provided to enclose an area of 100 Square feet out of bigger available space if required 3. Painting of the room including door, windows and grills. Distemping with oil bound washable distempers of approved brand and manufacturer for giving an even shade (Two or more coats.). 4. Almirahs -P/F up to 600 mm deep wooden cabinet, shutter with necessary fittings such hinges, tower bolt, handle etc. 5. Venetian blinds for sun facing windows. 6. Supply and installation of computer chairs as per approved make (4 in JSC & 2 CSR): 06 Nos. 7. Supply and installation of Computer tables as per approved make for CSR: 01 No. 8. Fire Extinguisher (For CSR): 01 No. 9. Air Conditioner (1.5) Ton with 4 KVA Stabilizer (in CSR): 01 No. <p>Electrical Work</p> <ul style="list-style-type: none"> • An electrical board as defined at "D" (3 in JSR & 5 CSR): 08 Nos. • Mirror Optic twin tube light fitting (2 in JSR & 4 in CSR) • Copper Plate earthing • All the wiring should be 3/20 copper wires for computers and lights etc. and 7/20 for air conditioners, server and UPS. • A 6 WAY MCBDB for UPS boards and two industrial power points for Air Conditioners and one for UPS. • Earthing wire should be 1/18 copper unit at CSR. 04 Nos. • Ceiling fans (2 in JSR & 2 IN CSR) • Provision for installing Air Conditioner unit at CSR: • Capacity: 1.5 Ton with 4KVA Voltage Stabilizer (For CSR): 01 No. 	<p>02 Nos.</p> <p>06 Nos.</p> <p>01 No.</p> <p>01 No.</p> <p>01 No.</p> <p>08 Nos.</p> <p>06 Nos.</p> <p>04 Nos.</p> <p>01 No.</p>

3.	Khunti	<p>Civil work</p> <ol style="list-style-type: none"> 1. Supply and installation of computer chairs as per approved make (4 in JSC & 2 CSR): 2. Supply and installation of Computer tables as per approved make for CSR: 3. Fire Extinguisher (For CSR): 4. Air Conditioner (1.5) Ton with 4 KVA Stabilizer (in CSR): <p>Electrical Work</p> <ul style="list-style-type: none"> • An electrical board as defined at "D" (3 in JSR & 5 CSR): • Mirror Optic twin tube light fitting (2 in JSR & 4 in CSR) • Copper Plate earthing • All the wiring should be 3/20 copper wires for computers and lights etc. and 7/20 for air conditioners, server and UPS. • A 6 WAY MCBDB for UPS boards and two industrial power points for Air Conditioners and one for UPS. • Earthing wire should be 1/18 copper unit at CSR. 04 Nos. • Ceiling fans (2 in JSR & 2 IN CSR) • Provision for installing Air Conditioner unit at CSR: • Capacity: 1.5 Ton with 4KVA Voltage Stabilizer (For CSR): 01 No. 	<p>06 Nos.</p> <p>01 No.</p> <p>01 No.</p> <p>01 No.</p> <p>04 Nos.</p> <p>01 No.</p>
----	--------	--	---

Terms & Conditions:

1. The work shall be executed as per the norms / specification of site preparation provided by NIC under the e-Courts Project.
2. This Court reserves the right to accept or reject any quotations without assigning any reason(s).
3. Validity of the quotation should be not less than 60 days.
4. The quantity of work may vary as per our actual requirement.
5. The interested firms may be allowed to visit the concerned sites after getting approval from the undersigned before submissions of quotation.
6. Rates in the quotation will be inclusive of all applicable taxes.

Sd/-
(Manoranjan Kavi)
C.P.C, E-Committee,
Jharkhand High Court, Ranchi.